

ITEM	PAYMENT REFERS	SHORT DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	SABS 1200A & PSA	SECTION 1: PRELIMINARY AND GENERAL				
1.3.5		Sub-Contractor's P&G				
1.3.6	(a)	Time related Items				
		Medicals for general labourers	No	5		
		PPE for general labourers (worksuit, gloves, safety boots, vests)	No	5		
		CARRIED FORWARD TO SUMMARY				

ITEM	PAYMENT REFERS	SHORT DESCRIPTION	UNIT	QTY	RATE	AMOUNT
3		SECTION 3: STORMWATER MANAGEMENT				
3.1	SABS1200DB & PSD & PSDB	Earthworks (Pipe Trenches)				
		Headwalls				
3.2.3	8.2.8	Inlet headwalls complete as per details including excavation for daylighting, shoring where required and backfilling all laid to tie in with design and existing levels for: a) 600mm diameter pipes	No	10		
	8.2.8	Outlet headwalls complete as per details including excavation for daylighting, shoring where required and backfilling all laid to tie in with design and existing levels for: a) 600mm diameter pipes	No	10		
3.3	SABS1200MK	Lined Drains				
3.3.1	8.2.8 8.2.9 8.2.10	Supply, Construct grouted stone pitching V Drain complete as per the detail including shuttering and all jointing for: 1) Type 1 - 1200mm wide	m ²	550		
	COTO 2100					
		CARRIED FORWARD TO SUMMARY				

ITEM	PAYMENT REFERS	SHORT DESCRIPTION	UNIT	QTY	RATE	AMOUNT
4	2200	SECTION 4: PREFABRICATED CULVERTS				
4.1	22.01	Excavation: (a) Excavating soft material situated within the following depth ranges below the surface level: (i) 0 m up to 1,5 m	m ³	80		
4.2	B 22.02	Backfilling: (b) Using imported selected material: (i) Granular material	m ³	130		
4.6		Gabions And Pitching				
4.6.1	SABS 1200D	Earthworks 8.3.2 (a) Excavate in soft material, backfill, compact to 93% Mod. AASHTO minimum density and dispose of surplus and unsuitable material for gabions or reno-matress.	m ³	60		
4.6.2	SABS 1200D 8.3.4 (a)	Backfilling Extra-over for importation of material from from borrow pits.				
		CARRIED FORWARD				

ITEM	PAYMENT REFERS	SHORT DESCRIPTION	UNIT	QTY	RATE	AMOUNT
		BROUGHT FORWARD				
4.6.3	SABS 1200DK	Gabions and Pitching				
4.6.3.1		Surface preparation for stone pitching, bedding of gabions or reno-mattress.	m ²	500		
4.6.3.2	8.2.2 PSDK 8.2.2	Gabion baskets and reno mattresses to be 2,7mm double twist wire dipped plastic coated wire cages of 80mm x 100mm aperture including plastic coating. Baskets to be filled with blue tillite gabion stone of dimensions 100mm to a) 3,0m x 1,0m x 1,0m gabion basket b) 6,0m x 1,0m x 0,23m reno mattress	m ³ m ³	25		Rate Only
4.6.3.3	8.2.4	A2 geofabric to foundation, sides and back of gabion walls and reno mattresses and all subsoil drains.	m ²	24		
4.8	COTO 51,02	Riprap: (a) Packed riprap 50 kg rock	m ³	65		
		CARRIED FORWARD TO SUMMARY				

ITEM	PAYMENT REFERS	SHORT DESCRIPTION	UNIT	QTY	RATE	AMOUNT
5		<u>SECTION 5: ANCILLARY ROAD WORKS</u>				
5.1	SABS1200MM 8.3.6	<u>Road signs</u> Supply and erect road signs all inclusive of the following: Symbols, characters, legend and borders and engineering grade retro reflective material, backing bracing for the sign, support poles in 60mm diameter galvanised steel tubing, concrete base, excavation and backfilling for: a) Stop signs (R1-600mm across flat) b) School Ahead signs (R3-600mm across flat) c) Narrow Bridge signs (W326) d) T Junction Chevron Sign (W409) e) Speed Limit f) Danger Plates (W401/402) g) Combined Curves Sign (W210) h) Sharp Curve Ahead i) T Junction Sign (W104)	No No No No No No No No No	2 1 2 2 2 10 2 2 2		
5.2		<u>Guardrails</u>				
5.2.1	SABS1200MM 8.2.1	Supply and construct galvanized guardrails, completely painted with posts (spaced to suit the standard length of guardrail), spacer blocks, bolts, nuts, washers, reinforcing plates inclusive of excavation and backfilling post holes and disposing of surplus excavated material to an approved dump site	m	65		
		CARRIED FORWARD TO SUMMARY				

FINAL SUMMARY PAGE

SECTION	DESCRIPTION	AMOUNT
1	PRELIMINARY AND GENERAL	R -
2	ROADWORKS	
3	STORMWATER MANAGEMENT	R -
4	BOX CULVERT	R -
5	ANCILLARY WORKS	R -
	SUB-TOTAL	R -
	SUB-TOTAL	R -
	ADD : VAT (15%)	R -
	TOTAL	R -